New Enterprise Rural Electric Cooperative 3596 Brumbaugh Rd, New Enterprise, PA 16664 (814) 766-3221 or (800) 270-3177 x 4604 MOBILE HOME - UNDERGROUND SERVICE INSTALLATION Conductor and conduit Underground type meter base (200 furnished and installed by amp min.) and panel furnished and New Enterprise REC installed by member within 30 ft of mobile home Conduit firmly fastened with New Enterprise REC requires a minimum of two straps an expansion 3" joint be installed here. Grounding to -3" PVC schedule 80 or meet National rigid conduit bushing Trenching and backfilling by Electric Code installed by member prior consumer-member per New Requirements to service installation to disconnect **Enterprise specifications** *See NOTE #1 24" min. radius 90 degree sweep elbow (3" rigid or 24" min. + 36" max. schedule 40 PVC) elbow to be maintained at must rest on compacted all time soil or be supported to eliminate settlement 10 ft sections of 3"PVC Conduit required under schedule 40 or rigid conduit all roadways and the entire distance of the Grounding and bonding trench. requirements to meet the National Electrical Code. See NEC 250.24 and 250.56. Ground rod(s) furnished and installed by member.